



Testing Summary

Getac G140 Tablet Docking Station

(7160-2212-00, 7160-2212-04, 7160-2212-10, 7160-2212-14)

Summary of Tests Performed at Gamber-Johnson

Test Description	Test Parameters
Vibration – Operational Test date: July, 2026	Getac Developmental Testing Specification per Figure 1. Test duration is two hours along three mutually orthogonal axes – not simultaneously (6 hours total). - Unit is unlocked - OEM provided operating conditions
Vibration – Operational RF Connection Test date: July, 2026	Getac Developmental Testing Specification per Figure 1. Test duration is two hours along three mutually orthogonal axes – not simultaneously (6 hours total). - Unit is unlocked - OEM provided operating conditions - Test is performed simultaneously with operational test. - Test is monitored to record any breaks in RF connectivity during vibration.
Vibration – Non-Operational (Minimum Integrity) Test date: July, 2026	MIL-STD-810H, Method 514.8, Category 24, per Figure 514.8E-1. Test duration is one hour along three mutually orthogonal axes – not simultaneously (3 hours total). - Unit is unlocked - OEM provided operating conditions
Functional Shock - Operational Test date: July, 2026	MIL-STD-810H, Method 516.8, Procedure 1, 3 positive and 3 negative pulses each axis (vertical, longitudinal and transverse), 18 pulses 20G, 11ms, terminal sawtooth - Unit is unlocked
Mechanical Shock Safety - Non-Operational Test date: July, 2026	MIL-STD-810H, Method 516.8, Procedure 1, 3 positive and 3 negative pulses each axis (vertical, longitudinal and transverse), 18 pulses total. 40G, 11ms half sine - Unit is unlocked
Shock – Bump Test Test date: July, 2026	Getac Developmental Testing Specification Rev C. IEC 60068-2-27:2008. 1000 positive and negative pulses in the vertical axis, 2000 total. 25G, 6ms half sine - Unit is unlocked

An ISO 9001:2015 certified company

Gamber-Johnson LLC · 5001 Joerns Drive · Stevens Point, Wisconsin 54481
PHONE: 1-715-344-3482 · FAX: 1-715-344-5209 · EMAIL: gamberj@gamberjohnson.com ·
www.gamberjohnson.com



Cycle Testing – Non-Operational Test date: August, 2026	• 30,000 cycles of the docking connector, latching and locking mechanisms • 5,000 cycles were conducted manually.
Electrostatic Discharge – Operational Test date: Sept., 2026	• ISO 10605, Section 8, Table C.2, Category 2 – Direct Air Discharge

Summary of Tests Performed at Independent Facility

Test Description	Test Parameters
Humidity Test date: August, 2026	MIL-STD 810H, Method 507.6, Procedure II, Aggravated, Table 507.6 • Ten 24-hour cycles, temperature varied from 30°C to 60°C to 30°C at constant 95% relative humidity.
Thermal Shock Test date: August, 2026	MIL-STD 810H, Method 503.7, Procedure I-C • Three, 2-hour cycles from -40°C to 85°C to -40°C • Transition time one minute
Low Temperature: Storage Test date: August, 2026	MIL-STD 810H, Method 502.7, Procedure I • -51°C Non-Operating, 24-hour duration
Low Temperature: Operational Test date: August, 2026	MIL-STD 810H 502.7, Procedure II-Operation • -31°C Operating, 24 hour duration
High Temperature: Operational Test date: August, 2026	MIL-STD 810H, Method 501.7, Procedure II • 63°C Operating, five 24-hour cycles.
High Temperature: Storage Test date: August, 2026	MIL-STD 810H, Method 501.7, Procedure I • 71°C Operating, seven 24-hour cycles.
Shock – Crash Hazard Test date: May, 2026	SAE J1455, Section 4.11.3.5, per Figure 13 • Unit is unlocked

An ISO 9001:2015 certified company



EMC Testing Test date: June, 2026	EN 55032:2015/A11:2020 • CISPR 32 – Class B • FCC Part 15, Subpart B – Class B • ICES-003, Issue 7:2020 – Class B
EMC Testing Test date: June, 2026	EN 50498:2010

Other Certifications

Description
EN 50581:2012 RoHS2 Directive 2011/65/EU

An ISO 9001:2015 certified company

Gamber-Johnson LLC · 5001 Joerns Drive · Stevens Point, Wisconsin 54481
PHONE: 1-715-344-3482 · FAX: 1-715-344-5209 · EMAIL: gamberj@gamberjohnson.com ·
www.gamberjohnson.com